

## PRE-TERMINATED CABLES

# DES L2/L3

## Splittable frame for pre-terminated cables

- ▶ Multiple possible configurations in one frame size
- A small number of cables can be easily accommodated.
- Frame screws in AISI304 Stainless Steel
- Integrated gasket
- ▶ Strain relief according to EN 62444
- Sturdy construction IK10
- ▶ Up to IP66



| Model /<br>Code | Some possible configurations | Cut-out<br>[mm] | <b>Pcs</b><br>/ pack |
|-----------------|------------------------------|-----------------|----------------------|
| DES-L2_MPX      |                              | 40 x 18         | 10                   |
| DES-L3_MPX      |                              | 63 x 18         | 10                   |

KIT\_DES2 Set of 2 mounting screws in AISI304 10

he DES L2 and L3 splittable frames enable pre- terminated cables from 2 to 16mm in diameter to pass through enclosure walls, providing strong strain relief and water protection.

### Technical data

Material: PP+GF

Flammability: self-extinguishing acc. to UL94-V0

Temperature: -40°C... +155°C (static)

Features: halogens and silicones free


#### **Related products**

- Inserts SPP and SPP K
- Inserts SPP 2x
- Inserts SPP 4x





Dimensions [mm]



DES L3

